

Description	Use	Description	Quantity	Memo
PLANNING & COORDINATION		DIRECTION, OVERSITE, & ACQUISITION		JIM STEGMAN/STEGMAN CONSTRUCTION
PLANNING & COORDINATION		DIRECTION, OVERSITE, & ACQUISITION		DOUG DELAY/ALAN SCHMIDT CONSTRUCTION
LEGACY HOUSE SUPPORT		PLANNING, MARKETING, RECRUITMENT		CHARLEY WAYMAN & BRIAN MILLER
				BUILDING INDUSTRY ASSOC. OF NKY
EXCAVATION L		TRACK HOE & BOBCAT		RON KING and SONS +
CONCRETE M	FOOTERS	MATERIAL	16.5CuYd	ERNST CONCRETE (discounted) +
FOOTERS L	LABOR	INSTALL	1.00	RABE CONSTRUCTION
REBAR, BEAM, & POSTS M	FOOTERS/FOUNDATIONS	MATERIAL	70.00	M C STEEL
BEAM & POSTS L	SUPPORTS	INSTALL	1.00	M C STEEL
CONCRETE M	FOUNDATION	MATERIAL	30CuYd	ERNST CONCRETE (discounted) +
FOUNDATION WALLS L	LABOR	INSTALL	1.00	RABE CONSTRUCTION
CONCRETE M	BASEMENT FL	MATERIAL	14CuYd	ERNST CONCRETE (discounted) +
BASEMENT FLOOR L	LABOR	INSTALL	1.00	DEAKINS CONSTRUCTION
CONCRETE M	P, W, S, P	MATERIAL	6CuYd	IDEAL SUPPLY (walks)
PORCH, WALKS, STAIRS, PATIO	LABOR	INSTALL	1.00	
CONCRETE M	DRIVEWAY	MATERIAL	13CuYd	IDEAL SUPPLY
DRIVEWAY L	LABOR	INSTALL	1.00	
FOUNDATION WATERPROOF L	LABOR	INSTALL	1.00	JOHNSON WATERPROOFING +
WEATHERPROOF SHEATHING	LABOR	INSTALL	1.00	TRIMCO +
BRICK and MORTAR M	EXT 1ST FL	MATERIAL	TBD	STAR BUILDING MATERIALS
MONETERY DONATION		MATERIAL		CARTER LUMBER \$1000.00 +
MONETERY DONATION		MATERIAL		KELLY BROS. LUMBER \$1000.00 +
MONETERY DONATION		MATERIAL		MUELLER \$750
CARPENTRY LABOR L	LABOR	FRAMING	1.00	HEMSATH CONSTRUCTION
				GROSSER & CO.
1ST FLOOR SUB FLOOR M	BEAM PLT	2X6X14 TRT SPF	3.00	*
1ST FLOOR SUB FLOOR M	MUD PLT	2X4X14 TRT #2 GRADE	10.00	*

Description		Use	Description	Quantity	Memo
1ST FLOOR SUB FLOOR	M	JOISTS	2X10-16 KD YP	67.00	*
1ST FLOOR SUB FLOOR	M	MISC GLUE	CONST ADSV QT	7.00	CARTER LUMBER
1ST FLOOR SUB FLOOR	M	SUBFLOOR	3/4" OSB T&G	36.00	CARTER LUMBER
1ST FLOOR SUB FLOOR	M	SHIMS	SHIM PACK SHINGLES	2.00	*
1ST FLOOR SUB FLOOR	M	SILL SEALER	50'-3/8"X3 1/2" FOAM	3.00	*
1ST FLOOR EXT WALL	M	1ST FL STUDS	2X4X7'8 5/8 KD SPF	140.00	*
1ST FLOOR EXT WALL	M	BRACES	2X4X12 KD SPF	20.00	*
1ST FLOOR EXT WALL	M	GUARDRAIL	2X4X12 KD SPF	13.00	*
1ST FLOOR EXT WALL	M	PLTS	2X4X14 KD SPF	30.00	*
1ST FLOOR EXT WALL	M	HEADERS	2X10x14 KD YP	6.00	*
1ST FLOOR EXT WALL	M	MISC GLUE	ELMCO CONST ADSV QT	4.00	CARTER LUMBER
1ST FLOOR EXT WALL	M	SHEATHING	7/16"X4'X8' OSB	38.00	CARTER LUMBER
TRUSS DELIVERY	M	TRUSSES	TRUSS PACKAGE	1.00	PANEL BARN LUMBER
TRUSS CRANE	L	LABOR	PLACE TRUSSES	2.00	MC D CRANE & CONCRETE
2ND FLOOR EXT WALL	M	HEADERS	2X10X14 KD YP	6.00	*
2ND FLOOR EXT WALL	M	MISC GLUE	CONST ADSV QT	3.00	CARTER LUMBER
2ND FLOOR EXT WALL	M	SHEATHING	7/16"X4'X8' OSB	18.00	CARTER LUMBER
2ND FLOOR SUB FLOOR	M	SUBFLOOR	3/4" OSB T&G	18.00	CARTER LUMBER
ROOF LUMBER	M	GBL EXT	1X6 #3 KD WP 16'	12.00	*
ROOF LUMBER	M	TRUSS TIES	1X4X14' #3 SPRUCE	8.00	*
ROOF LUMBER	M	DORMER	2X4X10 KD SPF	4.00	*
ROOF LUMBER	M	R.G.	2X4X10 KD SPF	2.00	* (R.G. = reverse gable)
ROOF LUMBER	M	TRUSS BRACE	2X4X16 KD SPF	15.00	*
ROOF LUMBER	M	DORMER	2X6X10 KD SPF	6.00	*
ROOF LUMBER	M	R.G.	2X6X10 KD SPF	4.00	* (R.G. = reverse gable)
ROOF LUMBER	M	GBL EXT	2X6X14 KD SPF	5.00	*
ROOF LUMBER	M	PORCH BEAM	2X8X8 KD YP	4.00	*
ROOF LUMBER	M	R.G.	2X8X10 KD YP	1.00	* (R.G. = reverse gable)
ROOF LUMBER	M	DOF SHEATHIN	7/16X4X8 OSB	74.00	CARTER LUMBER
SHINGLE DELIVERY	M	ROOFING	15# ROOFING FELT	6.00	MUELLER
SHINGLE DELIVERY	M	ROOFING	3 TAB OR BETTER SHINGLES	22 SQ	WILLOUGHBY SUPPLY

Description		Use	Description	Quantity	Memo
SHINGLE DELIVERY	M	ROOFING	ICE AND WATER 3'X100'	1.00	MUELLER
SHINGLE DELIVERY	M	ROOFING	STARTER SHINGLE	3 SQ	WILLOUGHBY SUPPLY
SHINGLE DELIVERY	M	ROOFING	40' CONTINUOUS RIDGE VENT	1.00	MUELLER
ROOF SHINGLES	L	LABOR	INSTALL	1.00	TOTAL HOME CARE
INTERIOR WALLS	M	1ST FLOOR	2X4X7'-10 1/8" KD SPF	60.00	*
INTERIOR WALLS	M	ATTIC	2X4X8 KD WF	40.00	*
INTERIOR WALLS	M	BSMT	2X4X8 KD WF	40.00	*
INTERIOR WALLS	M	LATH	1X6X14 #3 KD WP	4.00	*
INTERIOR WALLS	M	OSHA RL	2X4X10 KD SPF	6.00	*
INTERIOR WALLS	M	ATTIC PLT	2X4X14 KD SPF	10.00	*
INTERIOR WALLS	M	BSMT	2X4X14 KD SPF	4.00	*
INTERIOR WALLS	M	PLTS	2X4X14 KD SPF	18.00	*
INTERIOR WALLS	M	PLUM	2X6X8 KD SPF	10.00	*
INTERIOR WALLS	M	PLUM	2X6X14 KD SPF	2.00	*
INTERIOR WALLS	M	BSMT	2X4X14 TRT #2 GRADE	4.00	*
INTERIOR WALLS	M	MISC GLUE	CONST ADSV QT	4.00	(purchased from Lowe's)
INTERIOR STAIRS	M	STAIRS	STRAIGHT CARP/LVT 15 RISE	2.00	SCHUTTE STAIRS +
INTERIOR STAIRS	L	LABOR	INSTALL STAIRS	1.00	
VINYL WINDOW	M	PER PLANS	PER SPECS	17.00	PELLA OF MONTGOMERY
WINDOW INSTALLATION	L	LABOR	INSTALL	1.00	
GARAGE DOORS	M	PER PLANS	8X7 INSULATED w GLASS INSERT	2.00	
INSTALL GARAGE DOOR	L	LABOR	INSTALL	1.00	
INSULATION MATERIAL	M	PER PLANS	FIBER GLASS BATT and FOAM	TBD	
INSULATION	L	LABOR	INSTALL	1.00	
BLOW CEILING INSULATION	L		BID ITEM	1.00	
BLOWER DR INSUL INSPECTIO			BLOWER DOOR TEST	1.00	
DRYWALL	M	MATERIAL	PER PLANS	TBD	CONTINENTAL BUILDING PRODUCTS
INSTALL DRYWALL	L	PER PLANS	WALLS AND CEILINGS	1.00	

Description	Use	Description	Quantity	Memo
FINISHING COMPOUND M	MATERIAL	PER SPECS	TBD	CONTINENTAL BUILDING PRODUCTS
FINISH DRYWALL L		DRYWALL FINISHING	1.00	
CLEAN BRICK L	LABOR	CLEANING PER BRICK CNT	8.29	
GUTTER, DOWNSPOUT, VALLEY	MATERIAL	PER PLANS	TBD	MARSH BUILDING PRODUCTS
ALUMINUM WRAP AND SOFFIT	MATERIAL	PER PLANS	TBD	MARSH BUILDING PRODUCTS
SHUTTERS AND GUTTER GUARDS	MATERIAL	PER PLANS	TBD	MARSH BUILDING PRODUCTS
INSTALL G, D, V, AW, and SOFFIT	LABOR	INSTALL	1.00	
INTERIOR TRIM PACKAGE M	PER PLANS	PER SPECS	TBD	
TRIM CARPENTER L	LABOR	TRIM CARPENTRY	1.00	
CARPET FLOOR M	MATERIAL	PER SPECS	TBD	
CARPET INSTALLATION L	LABOR	INSTALL	1.00	
INTERIOR DOORS M	DOORS	PER PLANS	1.00	
INTERIOR DOORS L		INSTALL	1.00	
EXTERIOR DOORS M	DOORS	PER PLANS	3.00	
EXTERIOR DOORS L	LABOR	INSTALL	1.00	
INT/EXT DOOR HARDWARE M	PER SPECS	HARDWARE	14.00	
DOOR HARDWARE L	LABOR	INSTALL	1.00	
CABINETS and HARDWARE M	PER PLANS	KIT, BATHS, & LAUNDRY	TBD	LEGACY KITCHENS
COUNTER TOPS M	PER PLANS	AS SPEC	TBD	KBR & OHIO VALLEY
INSTALL CABINETS & HDW.	LABOR	INSTALL	1.00	CRAFTSMAN BY DESIGN
INSTALL COUNTER TOPS L	LABOR	INSTALL		KBR & OHIO VALLEY
INTERIOR RAILS M	HANDRAILS	RAILINGS PER PLANS	2.00	
INSTALL RAILS L	LABOR	INSTALL HAND RAILS	1.00	
APPLIANCES M		PER PLANS	1.00	

Description	Use	Description	Quantity	Memo
INTERIOR PAINT M	PAINT	PER SPECS	1.00	
INTERIOR PAINT L	LABOR	INSTALL	1.00	
CERAMIC FLOOR M	PER PLANS	AS SPEC	TBD	
CERAMIC WALL M	PER PLANS	AS SPEC	TBD	
CERAMIC INSTALL L	LABOR	INSTALL	1.00	
EXTERIOR PAINT M	PAINT	PER SPECS	1.00	
PREP EXTERIOR FOR PAINT L	LABOR	PREPARE	1.00	
PAINT EXTERIOR L	LABOR	PAINT AS SPECED	1.00	
SHOWER DOOR M	PER SPECS	OBSCURE GLASS	1.00	
SHOWER DOORS L	LABOR	INSTALL	1.00	
PLUMBING		permitting	1.00	NEIHEISEL PLUMBING
PLUMBING M	PER PLANS	drain and vent piping	1.00	FLORENCE WINNELSON
PLUMBING M	PER PLANS	PER SPECS	TBD	
PLUMBING (under slab) L	LABOR	INSTALL	1.00	ROBERTSON PLUMBING
PLUMBING ROUGH L	LABOR	INSTALL	1.00	
PLUMBING FINISH L	LABOR	INSTALL	1.00	
PLUMBING FINAL L		INSPECTION	1.00	NEIHEISEL PLUMBING
HVAC M	PER PLANS	MATERIALS	1.00	
HVAC INSTALL L	LABOR	INSTALL	1.00	ARC ELECTRIC, HEATING, & AIR
HVAC FINAL L	LABOR	INSPECTION	1.00	ARC ELECTRIC, HEATING, & AIR
LOAD TOPSOIL M	TOPSOIL	AMT. AS REQUIRED	TBD	
LIGHTING M	PER PLANS	PER SPECS	1.00	WISEWAY SUPPLY FLORENCE
ELECTRIC M	PER PLANS	MATERIALS	1.00	
ELECTRIC ROUGH L	LABOR	ROUGH-IN	1.00	SECO ELECTRIC

Description		Use	Description	Quantity	Memo
ELECTRIC FINISH	L	LABOR	FINISH INSTALL	1.00	SECO ELECTRIC
ELECTRIC FINAL	L		INSPECTION	1.00	SECO ELECTRIC
SHELVING	M	CLOSETS	SHELVING	1.00	
INSTALL SHELVING	L	LABOR	INSTALL		
LVT FLOORING	M		LUXURY VINYL TILE	1.00	
LVT FLOORING	L		INSTALL	1.00	
LANDSCAPING	M	MATERIAL	PER PLAN	TBD	
LANDSCAPING	L	LABOR	INSTALL	1.00	STEGMAN LANDSCAPING
POWER WASH FLATWORK	L	CONCRETE	LABOR	1.00	
CERTIFICATE OF OCCUPANCY		PDS	INSPECTION	1.00	HONK

KEY
KEY

*
+

*
+

\$1000 from Kelly; purchased bal. from Kelly
donation letter sent